

CCS NATIONAL INSTITUTE OF AGRICULTURAL MARKETING
(An organization of Ministry of Agriculture and Farmers Welfare)
Kota Road, Bambala, Pratap Nagar, Jaipur-302033

S.NO. E- File no 131843, NIAM/04/09/2019/ 11097

DATED 22.10.2024

Short Term NIT Notice

The Director General CCS NIAM invites Short term/limited tender for “ **Provision of vermi compost pit, replacement of damaged AC sheet at nursery in CCS NIAM Jaipur** from the approved and eligible contractors of CPWD/MES/RAJASTHAN STATE PWD/PSU From Central Govt./State Govt. The interested agencies may submit their sealed quotations in the prescribed format in the office of Director General office till 04.11.2024 upto 3.00 PM . The description of work are as under:

S.No.	Description of items	Quantity	Unit	Rate	Amount
1	Dismantling roofing including ridges, hips, valleys and gutters etc., and stacking the material within 50 metres lead of: a)Asbestos Cement sheet	33.00	Sqm		
2	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	3.00	Cum		
3	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. a) All kinds of soil.	3.00	Cum		
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:				
	a) 1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources: 8 graded stone aggregate 40 mm nominal size derived from natural sources)	2.00	Cum		
	b) 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	1.00	Cum		






5	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: a) Cement mortar 1:6 (1 cement : 6 coarse sand)	1.00	Cum		
6	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundations and plinth in a) Cement mortar 1:3 (1 cement : 3 coarse sand)	2.00	Sqm		
7	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-Charge) of total coated thickness 0.50 mm (base metal of minimum 0.45 mm thickness with total coating thickness of 0.05mm) with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self-drilling /self-tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	33.00	Sqm		
8	12 mm cement plaster of mix : a) 1:6 (1 cement: 6 coarse sand)	3.00	Sqm		
9	15 mm cement plaster on rough side of single or half brick wall of mix: a) 1:6 (1 cement: 6 coarse sand)	3.00	Sqm		
10	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : a) Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture	20.00	Sqm		
11	Kota Stone work (machine cut edges in veneer work) for wall lining upto 10 m height, fixed with a grout of cement mortar 1:3 (1 Cement : 3 coarse sand) and jointed with Cement mortar 1:2 (1 cement : 2 stone dust) or by suitable adhesive of approved quality, including grinding with hand grinder on joints, rubbing and polishing complete.	33.00	Sqm		

[Handwritten signature]

	(To be secured to the backing and the sides by means of cramps and pins if required).				
	a) Pre polished kota stone slabs on exposed face.				
	i) 25 mm thick				
	Total				

General conditions and specifications for civil work

1. The estimated cost of the work is Rs. 1,53,234/-
2. The time allowed for completion of the work will be 30 Days from the date of award of work.
3. The work shall be carried out in accordance with the CPWD Specifications 2019 Vol. I to II (corrected up to the last date of submission/uploading of bid) hereinafter referred as CPWD Specifications.
4. The Agency shall remove from site all rubbish and debris generated during the works and keep site clean and tidy throughout the Contract Period. All the serviceable and non-serviceable (malba) material shall be segregated and stored separately. Malba, rubbish & other waste materials shall be disposed of as directed by Infra Committee.
5. All serviceable material shall be kept in safe custody of the Institute as per direction of Infra Committee.
6. Defect liability period is 6 months after date of completion of the work.
7. As a guarantee towards due performance and compliance of the contract work, the successful bidder (contractor) will deposit an amount equal to 5% of contract value and should be kept valid for a period of 6 months beyond completion of all the contractual obligation as security deposit by way of demand draft in favour of **Director General "NATIOANL INSTITUTE OF AGRICULTURAL MARKETING"** payable at **JAIPUR** drawn on any Nationalized Bank/Scheduled Bank and payable at JAIPUR within ten days of the issue of the Letter of notification of award.
8. The contractor shall get the shades of all types of paints, distemper, water proofing cement paint etc. approved from the Infra -in-charge before procurement of materials.
9. The work will be executed as per satisfaction of the Infra committee.
10. The quotation will be submitted in the prescribed format.
11. The agency will submit GST certificate with the quotation.
12. The agency will submit bill in 2 copies in the office after completion of work for payment.


 22/10/24
 Dy. Director (Infra)